

Pluggable installation in concrete

Deksel betondoos B80/40 Rood

· With protective cover.



Article no:	AT5305
EAN:	8712259599649
Length	300 mm
Width	70 mm
Height	10 mm
Material	Plastic
Halogen free	Yes
Type of fastening	Plug-in cover
Colour	Red
Model	Construction protective cover
Depth	10 mm
Shape	Rectangular
Sealable	No
With screws	No
For box-/housing length	300 mm
For box-/housing width	70 mm
With cable outlet	No
Dispatch	25

A large part of the installation can already be prefabricated in the concrete factory with the help of the Sparing boxes.

There is enough space in the floor and wall boxes to store the excess length of the prefab cabling. As soon as the hull has been placed, the installation is plugged together in the floor and wall parts. All flush-mounted and central boxes are also pre-wired, so the connection of the switches and sockets can be performed very quickly.

Non-load-bearing interior walls are powered from wired floor boxes. The flush-mounted boxes in these walls can therefore be connected quickly. Even more time savings are achieved by connecting the switches and sockets in these walls completely pluggable, by using prefab mounted switches and sockets in hollow wall boxes.

The floor boxes are also used as temporary storage for the cabling of the outgoing groups from the distribution board. As soon as the distribution board is mounted, it is simply pluggable connected.